

**CONCRETE BLOCK
GROUT FILL QUANTITIES**

Concrete Block Grout Fill Quantities

<u>Wall Construction</u>	<u>Cubic Measure of Void Volume Per 100 Square Feet of Wall Surface Area</u>	
<u>Item</u>	<u>Cubic Feet (CF)</u>	<u>Cubic Yards (CY)</u>
12" Stretchers	49.9	1.85
12" Corner Breakers	42.9	1.59
1:1 Blend of 12" Stretchers and 12" Corner Breakers	46.4	1.72
12" Retaining Wall Block	56.0	2.07
10" Stretchers	34.4	1.27
8" Stretchers	29.7	1.10
8" Corner Breakers	27.2	1.00
2:1 Blend of 8" Stretchers and 8" Corner Brakers	28.5	1.06
8" Retaining Wall Block	27.8	1.03
6" Stretchers	20.7	0.77

<u>Bond Beams & Lintels</u>	<u>Cubic Measure of Void Volume Per 100 Lineal (Running) Feet of Beam or Lintel</u>	
<u>Item</u>	<u>Cubic Feet (CF)</u>	<u>Cubic Yards (CY)</u>
12" Bond Beam Block With Center Web	27.2	1.00
12" Bond Beam Block Without Center Web	32.9	1.22
8" Bond Beam Block With Center Web	15.9	0.59
8" Bond Beam Block Without Center Web	21.2	0.79
8" U-Lintel Block	16.7	0.62
6" Bond Beam Block	21.1	0.78

Note:

Quantities represent calculated volumes. No allowance has been included for waste, settlement, workmanship, or other construction factors.