



ADJUSTABLE WALL TIE
INSULATION RETAINER

HORIZONTAL REINFORCING
WHEN REQUIRED

MORTAR DROP CONTROL
FLASHING MEMBRANE SURFACE
ADHERE TO SUBSTRATE

UNOBSTRUCTED
WEEP SYSTEM @ 600 MM O/C
PREFINISHED METAL DRIP EDGE
SET ON TWO BEADS OF SEALANT

10 MIN.
DRAINAGE TILE

ADAIR® LIMESTONE
MASONRY UNIT,
MIN. 25 MM AIR SPACE,
RIGID OR SEMI-RIGID
INSULATION (THICKNESS
DEPENDANT ON
REQUIRED R-VALUE),
AIR/VAPOUR BARRIER
MEMBRANE,
CONCRETE MASONRY
UNIT (CMU),
METAL FURRING (OPTIONAL),
GYPSUM WALLBOARD.

VERTICAL REINFORCING
IF REQUIRED

FLOOR BY OTHER

BUILDING PAPER

AIR/VAPOUR BARRIER

GRAVEL MOWING
STRIP



ARRISCRAFT
INTERNATIONAL
BUILDING STONE • BRICK • LIMESTONE

ARRISCRAFT • CADD

TITLE: FOUNDATION WALL/
BURIED MASONRY UNIT
(GRAVEL MOWING STRIP AND FRENCH DRAIN)

DATE DRAWN:
08/30/04

SCALE:
1:5

DRAWN BY:
LPS

DETAIL No:
CB AD09S

D005