



CALCIUM SILICATE MASONRY UNIT (CSMU),  
 MIN. 1" AIR SPACE,  
 RIGID OR SEMI-RIGID INSULATION (THICKNESS DEPENDANT ON REQUIRED R-VALUE),  
 AIR/VAPOR BARRIER MEMBRANE,  
 EXTERIOR SHEATHING,  
 STEEL STUD WALL,  
 GYPSUM WALLBOARD.

FLASHING MEMBRANE SURFACE ADHERE TO SUBSTRATE  
 MORTAR DROP CONTROL  
 UNOBSTRUCTED WEEP SYSTEM @ 24" O/C

PREFINISHED METAL DRIP EDGE SET ON TWO BEADS OF SEALANT

3/8 MIN.

HIGH SLUMP MASONRY GROUT

DRAINAGE TILE

STEEL TRACK FASTENER (SCREW SIZE IS DETERMINED BY LOAD SUPPORTED)

STEEL TRACK

AIR/VAPOR BARRIER BUILDING PAPER

GRAVEL MOWING STRIP

6" MIN.



**ARRISCRAFT**  
 INTERNATIONAL  
 BUILDING STONE • BRICK • LIMESTONE

**ARRISCRAFT • CADD**

TITLE: FOUNDATION WALL/  
 BURIED MASONRY UNIT  
 (GRAVEL MOWING STRIP AND FRENCH DRAIN)

DATE DRAWN:  
 08/30/04

SCALE:  
 3"=1'-0"

DRAWN BY:  
 LPS

DETAIL No:

SS 12R

**U004**