



WOOD BLOCKING
 BACKER ROD AND SEALANT
 BULLNOSE SILL
 CALCIUM SILICATE MASONRY UNIT (CSMU)
 MASONRY TIE OR MECHANICAL ANCHOR IN HEAD JOINT
 RAKE BACK MORTAR BETWEEN UNITS APPROX. 1" DEEP. COVER WITH BACKER ROD AND SEALANT TO PROTECT MORTAR

PREMANUFACTURED THERMALLY BROKEN ALUMINUM WINDOW ASSEMBLY
 SPRAY APPLIED FOAM INSULATING AIR SEAL ALL AROUND FRAME
 BACKER ROD AND SEALANT ALL AROUND THE FRAME
 WOOD BLOCKING

1" MIN.
 UNDERSILL FLASHING MEMBRANE C/W END DAMS, INSTALL TUBE VENTS AT CENTER OF BULLNOSE UNITS
 VENT @ 24" O/C

INSULATION RETAINER
 ADJUSTABLE WALL TIE

GYPSUM WALLBOARD
 STEEL STUD WALL,
 EXTERIOR SHEATHING,
 AIR/VAPOR BARRIER MEMBRANE,
 RIGID OR SEMI-RIGID INSULATION (THICKNESS DEPENDANT ON REQUIRED R-VALUE),
 MIN. 1" AIR SPACE,
 CALCIUM SILICATE MASONRY UNIT (CSMU).



ARRISCRAFT
 INTERNATIONAL
 BUILDING STONE • BRICK • LIMESTONE

ARRISCRAFT • CADD

TITLE:
BULLNOSE WINDOW SILL

DATE DRAWN:
 08/30/04

SCALE:
 3"=1'-0"

DRAWN BY:
 LPS

DETAIL No:

SS 12R

U021