



CALCIUM SILICATE BUILDING STONE, MIN. 1" AIR SPACE, RIGID OR SEMI-RIGID INSULATION (THICKNESS DEPENDANT ON REQUIRED R-VALUE), AIR/VAPOR BARRIER MEMBRANE, EXTERIOR SHEATHING, STEEL STUD WALL, GYPSUM WALLBOARD.

MORTAR DROP CONTROL

FLASHING MEMBRANE SURFACE ADHERE TO SUBSTRATE

UNOBSTRUCTED WEEP SYSTEM @ 24" O/C

PREFINISHED METAL DRIP EDGE SET ON TWO BEADS OF SEALANT

ADAIR® LIMESTONE MARBLE BASE COURSE

3/8 MIN.

6" MIN. COMPRESSIBLE BACKER ROD AND SEALANT

PREMOLDED EXPANSION JOINT FILLER

2% SLOPE MIN.

STEEL TRACK FASTENER (SCREW SIZE IS DETERMINED BY LOAD SUPPORTED)

STEEL TRACK

BUILDING PAPER

HIGH SLUMP MASONRY GROUT



ARRISCRAFT
INTERNATIONAL
BUILDING STONE • BRICK • LIMESTONE

ARRISCRAFT • CADD

TITLE: FOUNDATION WALL/
BURIED MASONRY UNIT
(ADAIR® LIMESTONE BASE COURSE) WITH PAVING

DATE DRAWN:
08/30/04

SCALE:
3"=1'-0"

DRAWN BY:
LPS

DETAIL No:
SS LR4I

U006