



CALCIUM SILICAT
BUILDING STONE,
MIN. 1" AIR SPACE,
RIGID OR SEMI-RIGID
INSULATION (THICKNESS
DEPENDANT ON REQUIRED
R-VALUE),
AIR/VAPOR BARRIER
MEMBRANE,
EXTERIOR SHEATHING,
STEEL STUD WALL,
GYPSUM WALLBOARD.

MORTAR DROP
CONTROL

FLASHING MEMBRANE
SURFACE ADHERE
TO SUBSTRATE

UNOBSTRUCTED
WEEP SYSTEM @ 24" O/C

PREFINISHED METAL DRIP
EDGE SET ON TWO
BEADS OF SEALANT

ADAIR® LIMESTONE
MARBLE BASE COURSE

3/8 MIN.

6" MIN.
COMPRESSIBLE BACKER
ROD AND SEALANT

PREMOLDED EXPANSION
JOINT FILLER

2% SLOPE MIN.

STEEL TRACK FASTENER
(SCREW SIZE IS
DETERMINED BY
LOAD SUPPORTED)

STEEL TRACK

BUILDING PAPER
HIGH SLUMP
MASONRY GROUT



ARRISCRAFT
INTERNATIONAL
BUILDING STONE • BRICK • LIMESTONE

ARRISCRAFT • CADD

TITLE: FOUNDATION WALL/
BURIED MASONRY UNIT
(ADAIR® LIMESTONE BASE COURSE) WITH PAVING

DATE DRAWN:
08/30/04

SCALE:
3"=1'-0"

DRAWN BY:
LPS

DETAIL No:
SS SH2I

U006